

Praetoria Group / Praetoria Operation Group Inc.

Working Quotation Review - Labour Only

Internal working draft for site review and app entry

Date Prepared	May 06, 2026
Customer / Property	
Prepared By	Praetoria Group
Quote Type	Labour only - customer supplies materials unless agreed in writing
Status	Review draft - confirm scope before final customer quote

Quote Summary

Basement / Downstairs labour subtotal	\$26,050.00
Upstairs labour subtotal	\$5,350.00
Total without optional Bedroom #2 basement window	\$31,400.00
Optional / pending Bedroom #2 basement window	\$950.00
Total with optional Bedroom #2 basement window	\$32,350.00

- Important: This is a working review draft, not a final invoice. Confirm measurements, access, material availability, and site conditions before finalizing.
- Pricing is labour-only. Customer supplies all materials unless Praetoria Group agrees otherwise in writing.
- Taxes are not included unless added separately in the app.
- Additional charges may apply for hidden damage, prep work, disposal, permit requirements, electrical/plumbing/HVAC changes, material pickup, or work not listed here.

Section Review Checklist

Review	Floor / Area	Section	Subtotal	Notes / Corrections
[]	BASEMENT / DOWNSTAIRS	Kitchen	\$2,550.00	_____
[]	BASEMENT / DOWNSTAIRS	Bedroom #1	\$2,425.00	_____
[]	BASEMENT / DOWNSTAIRS	Sump Pump Room / Pump Room	\$2,750.00	_____
[]	BASEMENT / DOWNSTAIRS	Bedroom #2	\$2,850.00	_____
[]	OPTIONAL / PENDING CONFIRMATION	Bedroom #2 Optional Window	\$950.00	_____
[]	BASEMENT / DOWNSTAIRS	Laundry Room	\$825.00	_____
[]	BASEMENT / DOWNSTAIRS	Bathroom / Bar Room Area	\$7,650.00	_____
[]	BASEMENT / DOWNSTAIRS	Stairs Area	\$3,600.00	_____
[]	BASEMENT / DOWNSTAIRS	Hallway to Washroom / Bulkhead Ceiling Work	\$3,400.00	_____
[]	UPSTAIRS	Main Upstairs - Kitchen / Dining / Living / Hallway	\$1,050.00	_____
[]	UPSTAIRS	Bedroom #1 Upstairs	\$250.00	_____
[]	UPSTAIRS	Bedroom #2 Upstairs	\$250.00	_____
[]	UPSTAIRS	Upstairs Bathroom	\$1,750.00	_____
[]	UPSTAIRS	Master Bedroom Upstairs	\$350.00	_____
[]	UPSTAIRS	Upstairs Closet Doors / Strips	\$1,700.00	_____

BASEMENT / DOWNSTAIRS

Kitchen

Review	Line Item	Description / Included Labour	Price	Notes
[]	Kitchen Baseboard Installation	Install kitchen baseboards, cut to fit, cope/mitre corners where needed, fasten, and prep for finish. Customer supplies materials.	\$450.00	
[]	Small Kitchen Window Installation	Install small kitchen window into existing opening: fitting, leveling, fastening, and interior finishing prep. Excludes major framing, exterior waterproofing, siding, concrete cutting, and permits.	\$850.00	
[]	Kitchen Window Casing / Trim	Install casing/trim strips around small kitchen window; cut/mitre, fasten, and prep for caulking/paint.	\$350.00	
[]	Kitchen Trim Cutting & Installation	Cut and install kitchen trim pieces as needed to complete kitchen area and finish edges/openings.	\$400.00	
[]	Minor Kitchen Repairs / Completion Work	Minor repairs to complete kitchen area project: small patching, adjustments, fastening, finishing prep, and cleanup labour.	\$500.00	

Section subtotal: \$2,550.00

BASEMENT / DOWNSTAIRS

Bedroom #1

Review	Line Item	Description / Included Labour	Price	Notes
[]	Bedroom #1 Closet Door Installation	Install regular customer-supplied closet doors; fit, align, fasten, adjust, and confirm proper operation.	\$450.00	_____
[]	Small Basement Bedroom Window Installation	Install small basement bedroom window into existing opening. Excludes major framing, exterior waterproofing, concrete cutting, siding, and permits.	\$950.00	_____
[]	Bedroom Door Lock Installation	Install customer-supplied bedroom door lock/handle set, including basic drilling/fitting if required and latch adjustment.	\$225.00	_____
[]	Ceiling Vent Adjustment / Repair	Work on ceiling vent area; adjust/secure vent cover or opening and complete minor repair around vent.	\$350.00	_____
[]	Minor Ceiling Repairs	Patch, repair, and prep minor ceiling damage around vent/work area. Excludes major drywall replacement, texture matching, and painting unless separately listed.	\$450.00	_____

Section subtotal: \$2,425.00

BASEMENT / DOWNSTAIRS

Sump Pump Room / Pump Room

Review	Line Item	Description / Included Labour	Price	Notes
[]	Ceiling Vent Connection / Air Circulation Work	Connect/adjust ceiling vent so air circulation can work properly in the sump pump room. Excludes major HVAC ductwork/mechanical changes.	\$450.00	
[]	Complete Flooring in Pump Room	Complete flooring inside small pump room; cut/fitting around tight areas and finish edges. Customer supplies flooring/materials.	\$650.00	
[]	T-Bar Ceiling Installation - Pump Room	Install suspended T-bar/grid ceiling and ceiling tiles after vent work is completed. Customer supplies grid, tiles, hangers, wire, fasteners, and materials.	\$1,250.00	
[]	Minor Pump Room Finishing / Completion Work	Minor patching, adjustments, fastening, cleanup, and completion work needed to finish the pump room area.	\$400.00	

Section subtotal: \$2,750.00

BASEMENT / DOWNSTAIRS

Bedroom #2

Review	Line Item	Description / Included Labour	Price	Notes
[]	Carpet Installation - Bedroom #2	Install customer-supplied carpet in Bedroom #2; cutting, fitting, stretching/placement, and finishing edges. Customer supplies carpet, underpad, tack strips, transitions, and materials.	\$950.00	
[]	Closet Door Cut-Down / Modification	Cut down closet door to suit existing opening height; careful measuring, trimming, refitting, and adjustment. Custom-fit technical work.	\$500.00	
[]	Closet Door Trim / Casing	Install trim/casing around closet door opening; cut, fit, mitre, fasten, and prep for caulking/paint.	\$450.00	
[]	Baseboard Installation / Reinstallation	Install or reinstall baseboards after carpet work; cut, fit, fasten, and finish around room edges. Some existing baseboards may be reused where suitable.	\$550.00	
[]	Minor Bedroom #2 Completion Repairs	Minor finishing repairs, small adjustments, patching, fastening, and cleanup labour required to complete Bedroom #2.	\$400.00	

Section subtotal: \$2,850.00

OPTIONAL / PENDING CONFIRMATION

Bedroom #2 Optional Window

Review	Line Item	Description / Included Labour	Price	Notes
[]	Small Bedroom Window Installation - Pending	Optional/pending small bedroom window installation. Customer not fully sure yet. Excludes major framing, concrete cutting, exterior waterproofing, siding, and permit issues.	\$950.00	

Note: Optional item should be accepted only if customer confirms the window work.

Section subtotal: \$950.00

BASEMENT / DOWNSTAIRS

Laundry Room

Review	Line Item	Description / Included Labour	Price	Notes
[]	Complete Small Flooring Area	Complete small remaining flooring section in laundry room; measure, cut, fit, and finish small flooring area. Customer supplies materials.	\$450.00	
[]	Transition Strip Installation	Install customer-supplied transition strip; cut to fit, fasten, and adjust.	\$225.00	
[]	Minor Laundry Finishing / Completion Work	Minor adjustments, fastening, cleanup, and finishing required to complete laundry flooring area.	\$150.00	

Section subtotal: \$825.00

BASEMENT / DOWNSTAIRS

Bathroom / Bar Room Area

Review	Line Item	Description / Included Labour	Price	Notes
[]	Vanity Installation	Install customer-supplied vanity; position, level, secure, basic fitment, and finish prep. Excludes plumbing alterations, drain/supply-line relocation, and electrical work unless separately quoted.	\$750.00	_____
[]	T-Bar Ceiling Installation - Bathroom / Bar Room	Install suspended T-bar/grid ceiling and ceiling tiles in bathroom/bar room area. Customer supplies grid, tiles, hangers, wire, fasteners, and materials.	\$1,450.00	_____
[]	Window Framing / Window Trim	Frame and trim around bathroom/bar room window; measure, cut, fit, install casing/trim, and prep for caulking/paint.	\$650.00	_____
[]	Tile Around Hot Tub Area / Walls	Tile around hot tub wall area to customer-approved start and finish points; layout, cutting, setting tile, and basic finishing. Customer supplies tile, thinset, grout, edging/trim, waterproofing, spacers, and supplies.	\$3,500.00	_____
[]	Caulking / Sealing Bathroom-Bar Area	Caulk and seal finished areas around vanity, tile edges, hot tub area, window trim, and other required joints for finished appearance.	\$650.00	_____
[]	Minor Bathroom-Bar Completion Repairs	Minor patching, fitting, adjustments, fastening, cleanup, and final completion work needed to bring the area to a finished product.	\$650.00	_____

Section subtotal: \$7,650.00

BASEMENT / DOWNSTAIRS

Stairs Area

Review	Line Item	Description / Included Labour	Price	Notes
[]	Install Stair Bullnose / Stair Nosing - 12 Steps	Install customer-supplied bullnose/stair nosing on 12 stair treads; measure, cut, fit, adhesive/fastening as required, and finish adjustment.	\$1,500.00	
[]	Install Flooring on Stair Platform / Landing	Install small flooring section on stair platform/landing area between stair sections; cut, fit, and finish edges. Customer supplies materials.	\$750.00	
[]	Baseboard Installation / Finishing - Stair Area	Install or finish baseboards around stair area and landing; cut, fit, fasten, and finish around stairs/platform area.	\$850.00	
[]	Stair Area Minor Finishing / Completion Work	Minor repairs, adjustments, fastening, caulking prep, and completion work needed around stair flooring, nosing, and baseboard areas.	\$500.00	

Section subtotal: \$3,600.00

BASEMENT / DOWNSTAIRS

Hallway to Washroom / Bulkhead Ceiling Work

Review	Line Item	Description / Included Labour	Price	Notes
[]	Drywall Ceiling / Bulkhead Work	Repair/install drywall ceiling and bulkhead area in hallway leading to washroom; measure, cut, fasten drywall, form around bulkhead, and prep for finishing.	\$1,650.00	_____
[]	Bulkhead Repair / Finishing	Repair and finish bulkhead area as required to bring hallway ceiling/bulkhead to completed condition. Excludes major framing changes unless separately quoted.	\$950.00	_____
[]	Door Knob / Door Hardware Repair & Installation	Repair and/or install customer-supplied door knobs/door hardware as required in basement floor area; fit, fasten, latch adjustment, and function check.	\$350.00	_____
[]	Minor Hallway Completion Repairs	Minor patching, adjustment, sanding prep, fastening, and cleanup required to complete hallway/bulkhead area.	\$450.00	_____

Section subtotal: \$3,400.00

UPSTAIRS

Main Upstairs - Kitchen / Dining / Living / Hallway

Review	Line Item	Description / Included Labour	Price	Notes
[]	Install Blinds - Kitchen, Dining & Living	Install customer-supplied blinds/window coverings: 2 kitchen, 2 dining, and 3 living area blinds = 7 blinds total. Includes measuring, mounting brackets, leveling, fastening, and function check.	\$875.00	
[]	Hallway Vent Cover Replacement	Remove/replace hallway vent cover with customer-supplied vent cover; fit, fasten, and adjust.	\$175.00	

Section subtotal: \$1,050.00

UPSTAIRS

Bedroom #1 Upstairs

Review	Line Item	Description / Included Labour	Price	Notes
[]	Install Blinds / Window Covers - Bedroom #1	Install 2 customer-supplied blinds/window covers; measure, mount, level, fasten, and function check.	\$250.00	

Section subtotal: \$250.00

UPSTAIRS

Bedroom #2 Upstairs

Review	Line Item	Description / Included Labour	Price	Notes
[]	Install Blinds / Window Covers - Bedroom #2	Install 2 customer-supplied blinds/window covers; measure, mount, level, fasten, and function check.	\$250.00	

Section subtotal: \$250.00

UPSTAIRS

Upstairs Bathroom

Review	Line Item	Description / Included Labour	Price	Notes
[]	Install Bathroom Window Cover / Blind	Install 1 customer-supplied bathroom window cover/blind; measure, mount, level, fasten, and function check.	\$150.00	_____
[]	Tile Around Vanity Area	Tile around upstairs vanity area to customer-approved start and finish points; layout, cutting, setting tile, and basic finishing. Customer supplies tile, thinset, grout, edging/trim, spacers, and related materials.	\$1,250.00	_____
[]	Install Cover Strip / Trim Around Vanity Gap	Install customer-supplied strip/trim to cover exposed wood/gap area beside or around vanity; measure, cut, fit, fasten, and prep for finish.	\$350.00	_____

Section subtotal: \$1,750.00

UPSTAIRS

Master Bedroom Upstairs

Review	Line Item	Description / Included Labour	Price	Notes
[]	Install Large Master Bedroom Blind - Option A	Install 1 large customer-supplied blind on master bedroom window; careful measuring, bracket installation, leveling, fastening, and function check.	\$350.00	
[]	Alternative: Install Two Smaller Master Blinds - Option B	If customer supplies 2 smaller blinds instead of 1 large blind, install both. Use as alternate price, not additional unless both options are required.	\$300.00	

Use Option A or Option B, not both, unless the customer asks for both installations. The quote summary uses Option A at \$350.00.

Section subtotal used in total: \$350.00 (Option A)

UPSTAIRS

Upstairs Closet Doors / Strips

Review	Line Item	Description / Included Labour	Price	Notes
[]	Install Upstairs Closet Doors	Install customer-supplied closet doors upstairs; fit, align, fasten, adjust, and function check.	\$750.00	
[]	Install Closet Door Strips / Trim	Install customer-supplied strips/trim around closet door area; measure, cut, fit, fasten, and prep for finish.	\$450.00	
[]	Minor Upstairs Completion Repairs	Minor finishing, adjustments, fastening, touch-up prep, and completion work required to leave upstairs areas finished.	\$500.00	

Section subtotal: \$1,700.00

Quote Notes / Protection Language

Labour-only pricing: Customer is responsible for supplying all finish materials, fixtures, blinds, flooring, carpet, underpad, baseboards, trim, casing, doors, hardware, windows, vent covers, tile, thinset, grout, waterproofing materials, T-bar grid, ceiling tiles, fasteners, caulking, paint, and other materials unless Praetoria Group agrees otherwise in writing.

Scope control: This quotation covers only the listed labour items. Any work not listed is excluded unless added by written change order or approved add-on.

Site condition allowance: Pricing assumes existing openings, framing, walls, floors, stair structure, and surfaces are suitable for installation. Hidden damage, uneven surfaces, missing backing, rot, mould, water damage, electrical/HVAC conflicts, plumbing changes, structural repairs, or permit issues may require additional charges.

Flooring and trim: Floor leveling, old flooring removal, disposal, adhesive removal, subfloor repair, transition material, stair nosing materials, baseboard material, caulking, painting, and touch-ups are excluded unless listed separately.

Windows and exterior work: Window pricing assumes existing openings are usable. Concrete cutting, exterior waterproofing, siding/stucco repair, flashing, major framing, egress compliance work, and permits are excluded unless listed separately.

Tile and wet areas: Tile work assumes surfaces are ready. Waterproofing, backer board, substrate repair, plumbing relocation, and specialty materials are excluded unless listed separately.

Final pricing: Final quote may change after site walkthrough, measurements, customer material selection, and confirmation of the exact finish standard.

Customer Review Notes
